


AVRO AIRCRAFT LIMITED  
Inter-Departmental Memorandum

Ref 7766/16A/J  
Date April 1, 1958  
To S. E. Harper  
From J. D. Hodge  
Subject AIR CONDITIONING ENGINEERING TESTS

Herewith R.F.T. No. 5045 "Air Conditioning Engineering Tests"  
which lists the testing required to establish the operation of  
the Arrow 1 Air Conditioning System.

AA\*bb

  
J. D. Hodge  
Technical Flight  
Test Co-ordinator

C.C.  
Messrs J. Chamberlin  
F. Brame  
C. Lindow  
C. Marshall  
D. Scard (6)  
J. Lynch  
J. Gale  
F. Mitchell  
G. Shaw  
P. Martin  
J. Ames  
J. Booth  
S. Whiteley  
J. Scott  
D. Rogers  
D. Ridler

W/C G. Waterman  
W/C G. Waterman (2)

AVRO T.S.D. RCAF  
for transmittal to  
S/L K. Owen, C.E.P.E.  
Detachment.

Central Files



AVRO AIRCRAFT LIMITED

MALTON, ONTARIO

# REQUISITION FOR FLIGHT TEST

R.F.T. NO. 5045  
SHEET NO. 1 OF         
DATE: April 1, 1958

AIRCRAFT 25201 25202 and/or 25203	ASSIGNMENT NO. X73-384	WORK ORDER NO.
--	------------------------	----------------

## AIR CONDITIONING ENGINEERING TESTS

### 1. OBJECT

To prove the operation of the Arrow 1 Air Conditioning System.

### 2. INSTRUMENTATION

All instrumentation as called for in Report No. FAR/C105/1 Section 6 (Issue 8) is required for these tests. For convenience a copy of this section is included with this R.F.T.

### 3. PROCEDURE

3.1 It is required to have continuous recording of the following quantities at all times throughout flight.

- 3.1.1 Engine bleed static pressure (port engine)
- 3.1.2 Engine bleed temperature (port engine)
- 3.1.3 Turbine inlet total pressure
- 3.1.4 Turbine inlet temperature
- 3.1.5 Turbine outlet static pressure
- 3.1.6 Turbine outlet temperature
- 3.1.7 Turbine R.P.M.
- 3.1.8 Cabin inlet temperature
- 3.1.9 Cabin outlet temperature
- 3.1.10 Equipment inlet temperature

NOTE:— The measurement of these quantities will establish whether the air conditioning system is working efficiently or not. Should any problems arise it will be necessary to record all data as shown in the instrumentation list.

R.F.T. PREPARED BY: <i>A. H. H. H.</i>	APPROVED BY: <i>J. H. H.</i>	AUTHORIZED BY: <i>J. H. H.</i>
DATE FOR COMPLETION	PRIORITY	ESTIMATED COMPLETION DATE:



AVRO AIRCRAFT LIMITED

MALTON, ONTARIO

REQUISITION FOR FLIGHT TEST

R.F.T. NO. 5045

SHEET NO. 2 OF 2

DATE: April 1, 1958

25201 AIRCRAFT 25202 and/or 25203	ASSIGNMENT NO. <u>X73-384</u>	WORK ORDER NO.
---	-------------------------------	----------------

3.2 When proper operation of the system has been established recordings of all data are required for three flight cases, to check the theoretical calculations already made. These ~~three~~ cases are as follows:-

3.2.1 Subsonic cruise at 40,000'  $M = 0.92$

3.2.2 Maximum speed at maximum altitude

3.2.3 Cruise at sea level  $M = 0.4$

4. DATA REQUIRED

4.1 Recording of ~~ten~~ items as under Procedure section 3.1.

4.2 Recordings of all instrumentation for Procedure section 3.2.

R.F.T. PREPARED BY: <i>A. Henderson</i>	APPROVED BY:	AUTHORIZED BY:
DATE FOR COMPLETION	PRIORITY	ESTIMATED COMPLETION DATE:







## 2.1 Dynamic Pressure

### 2.1.1 Components

Instrument	Range (in)	Accuracy (in)	Accuracy (% of Range)	Recording Frequency
T1	+100 +1000	$\pm 10$	1%	1/sec
T3	-20 +400	$\pm 5$	1%	5/min
T4	-20 +250	$\pm 5$	2%	5/min
T5	-30 +100	$\pm 4$	2%	5/min
T6	0 +500	(to be built into turbine unit)		2/min
T7&8	-20 +130	$\pm 5$	3%	5/min
T8 (6 off)	0 +200	$\pm 2$	1%	
T9	0 +500	$\pm 10$	2%	5/min
T10	0 +600	$\pm 10$	2%	5/min
T11	0 +500	$\pm 10$	2%	5/min
T12	0 +140	$\pm 5$	3%	5/min

## 2.2 Static Pressure

Instrument	Range (psia)	Accuracy (psi)	Accuracy (% of Range)	Recording Frequency
P <sub>s</sub> 1	0-360	$\pm 10$	2%	1/sec
P <sub>s</sub> 2	0-100	$\pm 1$	1%	1/sec
P <sub>s</sub> 3	0-100	$\pm 1$	1%	5/min
P <sub>s</sub> 5 (rake)	0-20	$\pm 0.2$	1%	5/min
P <sub>s</sub> 7	0-20	$\pm 0.2$	1%	5/min
P <sub>s</sub> 8	0-20	$\pm 0.1$	0.5%	1/sec
P <sub>s</sub> 9 (rake)	0-20	$\pm 0.2$	1%	5/min *
P <sub>s</sub> 10 (rake)	0-20	$\pm 0.2$	1%	5/min *

\* Note: Either static or total may be measured.

(Continued.....)



## 2.3 Head Pressure

Measurement	Range	Accuracy (psi)	Accuracy (% of Range)	Recording Frequency
$\Delta P_3$	0-5 psi	$\pm 0.25$	5%	5/min
$P_{t4}$	0-100 psia	$\pm 1$	1%	5/min
$\Delta P_7$	0-1 psi	$\pm 0.05$	5%	5/min
$P_{t9}$ rake	0-30 psia	$\pm 0.3$	1%	5/min *
$P_{t10}$ rake	0-30 psia	$\pm 0.3$	1%	5/min *


\* See note Page 23.

## 2.4 Miscellaneous

In addition, it is required to measure turbine R.P.M., see location 6 in sketch. As in the case of bearing temperature, transducers will be built into the unit by AResearch.

The sampling rate required for turbine R.P.M. is 5/sec.





C-105 INSTRUMENTATION  
AIR-CONDITIONING SYSTEM  
ISSUE 8