

1. LUBRICATION (No Sketch)

Item	Range	Accuracy	Accuracy % of full range	Sampling Frequency
1. Port engine oil pressure	0 to 80 psi	± 2 psi	$\pm 4\%$	5/min
2. Stbd. engine oil pressure	0 to 80 psi	± 2 psi	$\pm 4\%$	5/min
3. Oil Temp at port engine inlet	-75 to +250°F	$\pm 6.5^\circ\text{F}$	$\pm 2\%$	2/min
4. Oil temp at Stbd. engine inlet	-75 to +250°F	$\pm 6.5^\circ\text{F}$	$\pm 2\%$	2/min
5. Port engine gearbox air/oil heat exchanger inlet temperature	-75 to +500°F	$\pm 10^\circ\text{F}$	$\pm 2\%$	2/min
6. Stbd. engine gearbox air/oil heat exchanger inlet temperature	-75 to +500°F	$\pm 10^\circ\text{F}$	$\pm 2\%$	2/min

2. ENGINE CONDITIONS (No Sketch)

7. Port engine power lever position ⁺	0 to 100 deg.	± 1 deg.	$\pm 1\%$	2/min
8. Stbd. engine power lever position ⁺	0 to 100 deg.	± 1 deg.	$\pm 1\%$	2/min
9. Port engine L.P. compressor R.P.M. [‡]	0 to 110%		$\pm 0.5\%$	12/min
10. Stbd. engine L.P. compressor R.P.M. [‡]	0 to 110%		$\pm 0.5\%$	12/min
11. Port engine H.P. compressor R.P.M. *	0 to 110%		$\pm 0.5\%$	12/min
12. Stbd. engine H.P. compressor R.P.M. *	0 to 110%		$\pm 0.5\%$	12/min
13. Port engine intake static pressure (P_{s2})	0 to 30 psia	± 0.3 psi	$\pm 1\%$	20/sec
14. Stbd. engine intake static pressure (P_{s2})	0 to 30 psia	± 0.3 psi	$\pm 1\%$	20/sec
15. Port engine intake total head pressure (P_{t2})	0 to 30 psia	± 0.3 psi	$\pm 1\%$	12/min
16. Stbd. engine intake total head pressure (P_{t2})	0 to 30 psia	± 0.3 psi	$\pm 1\%$	12/MIn

+ To be measured at the engine end of the flexible drive to the engine.

‡ Visual indication of both L.P. compressor speeds is required in pilot's cockpit if possible

* Visual indication of both H.P. compressor speeds is a definite requirements in the pilot's cockpit.

2. ENGINE CONDITIONS (cont'd)

Item	Range	Accuracy	Accuracy % of full range	Sampling Frequency
17. } 18. } 19. } 20. }	<u>DELETED</u>			
21. Turbine discharge press. (Pt ₇) Port	0 to 45 psia	±0.45 psi	±1%	12/min
22. Turbine discharge press. (Pt ₇) Stbd.	0 to 45 psia	±0.45 psi	±1%	12/min
23. Turbine discharge temp. (Tt ₇) Port.	0 to 1400° F	±14°F	±1%	12/min
24. Turbine discharge temp. (Tt ₇) Stbd.	0 to 1400° F	±14°F	±1%	12/min
25. L.F. compressor inlet temp. (Tt ₂) Port	<u>-75 to +350°F</u>	±4°F	±1%	12/min
26. L.F. compressor inlet temp. (Tt ₂) Stbd.	<u>-75 to +350°F</u>	±4°F	±1%	12/min
26a Bleed valve shut indication ++				Cont. ind.

++ Wiring provision only, to auto observer. For ground test only.

3. FUEL FLOW (no sketch)

27. Fuel weight flow to port engine	600 to 25,000 lb/hr	±125 lb/hr	±0.5%	12/min
28. Fuel weight flow to Stbd. engine	600 to 25,000 lb/hr	±125 lb/hr	±0.5%	12/min
29. Fuel temp. at inlet to port engine burner	<u>-75 to +350°F</u>	<u>±8°F</u>	±2%	2/min
30. Fuel temp. at inlet to stbd. engine burner	<u>-75 to +350°F</u>	<u>±8°F</u>	±2%	2/min

4. COOLING (see fig. 1)

(Port engine only except item no. 58 q.v.)

Unless otherwise stated, structural temperatures are required at the locations listed.

Item	Range	Accuracy	Accuracy % of full range	Sampling Frequency
31. Centre rear mount, station 711	0 to 1000°F	± 10°F	± 1%	1/min
32. Former below turbine (on upper flange)	0 to 500°F	± 5°F	± 1%	1/min
33. On hat section at T1-24ST shroud joint at Stn. 698	0 to 500°F	± 5°F	± 1%	1/min
34. Top inboard shroud (on outer surface of shroud) at Stn. 742	0 to 500°F	± 5°F	± 1%	1/min
35. Top inboard shroud (on outer surface of shroud) at Stn. 780	0 to 500°F	± 5°F	± 1%	1/min
36. Top of titanium former (shroud) at Stn. 803	0 to 500°F	± 5°F	± 1%	1/min
37. Shroud at bolt from lower latch at Stn. 803	0 to 500°F	± 5°F	± 1%	1/min
38. Top of shroud inner flange at Stn. 803	0 to 500°F	± 5°F	± 1%	1/min
39. Top of shroud inner flange at kink, Stn. 803	0 to 500°F	± 5°F	± 1%	1/min
40. Inner surface of slit on slit at Stn. 855	0 to 1000°F	± 20°F	± 2%	5/min
41. Inboard, shroud (on outer surface, on engine E) Stn. 836	0 to 500°F	± 10°F	± 2%	5/min
42. Air temp. top rear compressor, zone 1	0 to 500°F	± 5°F	± 1%	1/min
43. Air temp. under turbine, zone 2	0 to 500°F	± 5°F	± 1%	1/min
44. Air temp. above turbine, zone 2	0 to 500°F	± 5°F	± 1%	1/min
45. Air temp. above engine, zone 2, stn. 803	0 to 500°F	± 5°F	± 1%	1/min
46. Air temp. below engine, zone 2, stn. 803	0 to 500°F	± 5°F	± 1%	1/min
47. Ambient air temp. forward of parachute bay (not shown in fig)	0 to 500°F	± 5°F	± 1%	1/min
48. Engine can next centre rear mount, Stn. 710	0 to 1000°F	± 10°F	± 1%	1/min
49. Lower side of engine can, Stn. 710	0 to 1000°F	± 10°F	± 1%	1/min
50. Top flange of I-beam on E through heat exchangers Stn. 592	0 to 500°F	± 5°F	± 1%	1/min
51. Top flange of former directly below firewall, stn. 663	0 to 500°F	± 5°F	± 1%	1/min
52. Structure 3 1/2" aft of aux. ejector (inner surface of lower skin) Stn. 663	0 to 500°F	± 5°F	± 1%	1/min

W On beam, as near to top as possible

4. COOLING (cont'd)


Item	Range	Accuracy	Accuracy % of full range	Sampling Frequency
53. Blow-in doors outside of bend of lower hose, at Stn. 673	0 to 1000°F	± 10°F	± 1%	1/min
54. Lower longeron engine bay, Stn. 591 (Not shown in fig.)	0 to 500°F	± 5°F	± 1%	1/min
55. Bottom of light frame (on web) at Stn. 586 (Not shown in fig.)	0 to 500°F	± 5°F	± 1%	1/min
56. Bottom of light frame (on web) at Stn. 656 (Not shown in fig.)	0 to 500°F	± 5°F	± 1%	1/min
57. Gills shut indication lights, port, 2 * per engine	* One on side gills indicating "shut - not shut"; one on oil cooler gill, at the bottom, indicating "shut - fully open"	± 6°F	± 1%	Cont.
58. Gills shut indication lights, stbs. 2 * per engine				
58a Air temperature, alternator exhaust (Not shown in fig.)				
	75 to 500°F	± 6°F	± 1%	5/min

5. STATIC PRESSURES (see fig. 1.)

(Port engine only)

59. Top centre compressor, differential between zone 1 and 2.	5 to 20 psid	± 0.25 psi	± 1%	6/min
60. Zone 2, top rear compressor	0 to 35 psia	± 0.35 psi	± 1%	6/min
61. Zone 2, bottom mid section of tailpipe	0 to 35 psia	± 0.35 psi	± 1%	6/min
62. Differential between zone 2 and parachute bay at centre fuselage (not shown in fig.)	5 to 5 psid	± 0.1 psi	± 1%	6/min
63. Differential in ejector shroud, rel. to ambient. Between stns. 820 & 825 at bottom of shroud	3 to 0 psig†	± 0.05 psi	± 2%	6/min

† Actual differential pressure range may be -3 to +18 psi.



COOLING SYSTEM INSTRUMENTATION FOR J-75 ENGINE INSTALLATION