

I will supply two cases to be installed on the platform; these cases will be about eight feet (8') long, six feet (6') high, and two feet and six inches (2'- 6") deep. There will be two pipes installed in each of these two cases as hangers for suits and overcoats.

All of these five cases will be in the design of Monterey furniture and given an antique effect. For details of these cases, see plans. Also one mirror two feet by five feet (2' x 5') and one mirror two feet square (2' x 2').

On the lot at the north side of the building at the front I will erect a pergola about seven feet (7') high, eight feet (8') wide and ten feet (10') long.

This pergola will be fastened to the side of the building with a window cut through from that side. The walk of the pergola will have a flagstone effect and at the back end a veneered brick wall effect will be erected with wall fountain in center. There will also be a rear door and steps installed in this lot.

#### ELECTRIC WORK.

The entire store will be rewired with nine (9) outlets in the show windows, one (1) outlet in the vestibule, two (2) ceiling lights, two (2) bracket lights, two (2) base plugs, and one (1) bracket light on the outside of the building over the pergola.

There will also be provisions made for an electric sign. For the locations of all these outlets see plans.

#### DECORATING.

The walls of the entire sales department of the store will be in rough stucco, giving a rustic effect to beams and fixtures.

I would advise at this time that these specifications of the job be disregarded and the entire work be left to my best judgment, there being so many details of such work that it is almost impossible to mention them all. Such as color effect of walls, the painting of front transom, re-building of front door, fitting room in back of store, etc., etc.

I have done many jobs in this way and it has proven satisfactory for all parties concerned.

The cost of this work will be two thousand, five hundred and twenty dollars (\$2520.00).

One third of this amount to be paid upon the acceptance of this contract, one third to be paid when the work is half finished, and the balance to be paid when the job is completed according to the plans and these specifications.

I will use all existing materials possible and supply all