

Concerned Citizens for Washington Cemetery Care, Inc.
Monument Repair - Phase 3A
SCOPE OF WORK -- The Monument Company

10-Dec-96 Page 1 of 1

Lot No.	Name	No.	Size*	Scope*	Scope of Work	Cleaning	Repair
A-029	Underwood	1	L	F D R	Level on new foundation; drill & pin; repair large chip(?)	25	585
A-068	Herrmann	2	M	F D	Level on single new foundation; drill & pin	30	645
A-072	Williams	1	M	F D	Level on new foundation; drill & pin	15	320
A-080	Heath	2	M/L	F D	Level on new foundations; drill & pin	30	640
A-080	Heath	1	L	F D	Level on new foundation; drill & pin	25	370
A-080	Heath	1	S	F D	Level on new foundation; drill & pin	15	170
A-105	Blind	2	S	F D	Level on new foundations; drill & pin	30	465
A-105	Floyd	1	S	F D	Level on new foundation; drill & pin	15	170
A-112	Schrane	1	S	F D	Level on new foundation; drill & pin	25	220
B-131	Railway Conductors	1	XL	F D	Level on new foundation; drill & pin	35	485
B-131	Hansard	1	M	F D	Level on new foundation; drill & pin	—	180
C-027	Osterman	2	M	F D	Level on new foundations; drill & pin	50	565
F-075	Turner	1	S	F D	Level on new foundation; drill & pin	25	200
F-077	Finn	1	S	F D	Level on new foundation; drill & pin	15	200
Total		18				235	5,215
				Avg. cost:			
	Total Repairs	18		290		235	5,215
	Total, incl. cleaning			303			5,450

*Scope: F - Foundation D - Drill & Pin S - Shim R - Repair

*Size: S - Under 2 ft. tall M - 2-4 ft. L - 4 -6 ft. XL - Over 6 ft.

All joints to be secured by pinning and applying adhesive. No vehicle over 5 tons is permitted in the cemetery.

























