

Washington Cemetery Historic Trust
Monument Repair - Phase 4B
Natural Stone, Inc.

Rev. 1 15-Jul-98

Page 1 of 1

Size*	Scope*	Scope of Work	Cleaning	Repair	Pin Characteristics		
					Number of Pins	Pin Diameter	Hole Depth
M	S D	Shim on existing foundation; drill & pin	incl.	135	4	0	3
M	F D	Shim on existing foundation; drill & pin	incl.	135	4	0	3
M	D	Drill, pin, & rejoin on existing base & foundation	incl.	105	2	1	3
M	D R	Repair, drill, pin, & rejoin on existing base & foundation	incl.	310	4	0	3
M	D	Drill, pin, & rejoin on existing base & foundation	incl.	100	2	0	3
M	D	Drill, pin, & rejoin on existing base & foundation	incl.	165	4	0	3
M	S D	Shim on existing foundation; drill & pin	incl.	135	3	0	3
M	S D	Shim on existing foundations; drill & pin	incl.	135	2	0	3
L	S D	Shim on existing foundation; drill & pin	incl.	130	2	1	4
M	R	Repair on new limestone slab, per THC	incl.	380	--	--	--
S	R	Repair on new limestone slab, per THC	incl.	300	6	0	3
Average cost:		Number to be cleaned: 11	0	2,030			
185				2,030			
185				2,030			

D - Drill & pin
M - 2-4 ft.

S - Shim
L - 4 -6 ft.

R - Repair
XL - Over 6 ft.

C - cradle

! applying adhesive.

No vehicle over 5 tons is permitted in the cemetery.

Washington Cemetery Historic Trust
Monument Repair - Phase 4B
Natural Stone, Inc.

26-Apr-98

Page 1 of 1

Lot No.	Name	No.	Size*	Scope*	Scope of Work	Cleaning	Repair	Pin Characteristics		
								Number of Pins	Pin Diameter	Hole Depth
A-065	Moy	1	M	S D	Shim on existing foundation; drill & pin	incl.	135	4	0.375	3
A-097	Rabby	1	M	F D	Shim on existing foundation; drill & pin	incl.	135	4	0.375	3
A-125	Holdgraf	1	M	D	Drill, pin, & rejoin on existing base & foundation	incl.	105	2	0.5	3
B-042	Kelly	1	M	D R	Repair, drill, pin, & rejoin on existing base & foundation	incl.	310 ⁴⁹⁵	4	0.375	3
C-002	Molk	1	M	D	Drill, pin, & rejoin on existing base & foundation	incl.	100	2	0.375	3
C-031	Artz	1	M	D	Drill, pin, & rejoin on existing base & foundation	incl.	165	4	0.375	3
C-032	Dietrich	1	M	S D	Shim on existing foundation; drill & pin	incl.	135	3	0.375	3
C-035	Weeden	1	M	S D	Shim on existing foundations; drill & pin	incl.	135	2	0.375	3
C-060	Thompson	1	L	S D	Shim on existing foundation; drill & pin	incl.	130	2	0.5	4
C-128	McCarty	1	M	D R	Repair, drill, pin, & rejoin on existing base & foundation ^{add limestone}	incl.	300 ³⁵⁰			
S-340	Sandifer	1	S	F D R	Set into new limestone slab on new foundation, per THC	incl.	380	6	0.25	2.5
Total Repairs		11	Average cost: 185		Number to be cleaned: 11		0	2,030		
Total, including cleaning			185					2,030		

*Scope: F - Foundation

D - Drill & pin

S - Shim

R - Repair

*Size: S - Under 2 ft. tall

M - 2-4 ft.

L - 4 -6 ft.

XL - Over 6 ft.

C - cradle

All joints to be secured by pinning and applying adhesive.

No vehicle over 5 tons is permitted in the cemetery.

98-425

15 July 1998

Mr. Burt Ballanfant, President
WASHINGTON CEMETARY HISTORIC TRUST

Dear Mr. Ballanfant,

As per a listing dated 26 April 1998 (copy attached), describing the needed monument repairs for the Trust to complete "Phase 4B," we propose to perform the requested repairs, restoration and cleaning as described in the "Scope of Work." However, the price is now \$2,465.00 and not \$2,030.00. Our lead installer, Dennis Humphrey spoke with Bernice Mistrot concerning the repair to three of the proposed monuments needed repairs and restorations. The scope and process of the repairs has changed, will increase the contract amount. Also, these three monuments will require foundation work that will be provided by John Schlitzberger at Houston Monument Company. Charges for this work are not included in our contract. Changes/additions to the contract are listed below:

- | | |
|--|--------------------|
| 1) B-042 Kelly - Repair, re-set, add contrasting base pieces | 495.00 + 185.00 |
| 2) C-128 McCarty - Repair, re-set in limestone | 550.00 + 250.00 |
| 3) S-340 Sandifer - Repair, re-set in limestone | 380.00 (no change) |

On item number three, "Sandifer," there will be an additional charge for foundation repair. The three monuments listed above are currently in our shop and are being repaired. John Schlitzberger said that he would pick them up from here and then take care of the foundation work. We are ready to begin on site repairs and restoration the week of August 3rd. Please give me a call about a question concerning the "McCarty" Die.

Please indicate your acceptance of our proposal with your signature below.

Yours sincerely,

Roland P. St. Lawrence
President

Enclosures as noted

RPS:cas

Burt Ballanfant, President (Date)
For WASHINGTON CEMETARY HISTORIC TRUST





















