

Washington Cemetery Historic Trust
Monument Repair - Phase 5E
The Monument Company

Rev. 1 15-May-2000

8-Mar-2000

Page 1 of 1

Lot No.	Name	No.	Size*	Scope*	Scope of Work	Repair	Cleaning	Pin Characteristics		
								Number of Pins	Pin Diameter	Pin Length
C-005	Kumke	1	S	D	Drill, pin, & rejoin on existing base & foundation	80	25	1	0.750	6
C-016	Gaedke	1	M	D	Drill, pin, & rejoin smaller one on existing base & found.; clean both	40	50	1	0.750	8
C-150	Dickey	2	M	D	Drill, pin, & rejoin on existing bases & foundations	80	80	1	0.750	6
C-150	Wagner	1	M	D	Drill, pin, & rejoin on existing base & foundation (clean 2nd one)	80	80	1	0.750	6
D-114	McMahon	1	M	D	Drill, pin, & rejoin on existing base & foundation	160	40	2	0.563	8
F-079	Pruce	1	M	F	Level on new foundation (was repaired in Phase 2B)	250	25	2	0.750	6
F-079	Pruce	1	C	F	Straighten and clean cradle and coping	250	75	--	--	--
F-082	Praytor/Campbell	1	M	D	Drill, pin, & rejoin on existing base & foundation (add one pin)	120	40	1	0.750	12
F-082	Lewis	1	S	R	Repair two loose chunks, and rejoin	40	25	--	--	--
G-011	Lemkie/Florence	1	M	D	Drill, pin, & rejoin on existing base & foundation	60	25	1	0.750	16
G-012	Heinzelberger	1	L	D	Drill, pin, & rejoin on existing base & foundation (G-11 in photo)	80	25	1	0.750	24
G-018	Vanden	1	S/C	F D	Raise headstone & cradle; set on new foundation; drill and pin	400	25	2	0.500	6 (nylon)
G-022	Keister	1	M	D	Drill, pin, & rejoin on existing base & foundation	160	40	2	0.750	6
G-022	Pech	2	M	D	Drill, pin, & rejoin on existing bases & foundations; clean cradles	80	80	2	0.750	10
G-038	Belitz	1	M	D	Drill, pin, & rejoin on existing base & foundation	80	40	1	0.750	9
G-077	Davis	1	M	D	Drill, pin, & rejoin on existing base & foundation	80	40	1	0.750	10
G-083	Hayes	1	M	D	Drill, pin, & rejoin on existing base & foundation	80	40	1	0.750	6
G-086	Smith	1	M	D	Drill, pin, & rejoin on existing base & foundation	80	40	1	0.750	9
G-097	Wahlberg/Gustavson	3	M	D	Drill, pin, & rejoin on existing bases & foundations	320	120	4	0.750	6
G-098	Ward	1	S	D	Drill, pin, & rejoin on existing base & foundation	80	40	1	0.750	10
Average cost:										
Total Repairs		24		108	Number to be cleaned: 26	2,600	955			
Total, including cleaning				148			3,555			

955

*Scope: F - Foundation

D - Drill & pin

S - Shim

R - Repair

*Size: S - Under 2 ft. tall

M - 2-4 ft.

L - 4 -6 ft.

XL - Over 6 ft.

C - cradle

All joints to be secured by pinning and applying adhesive.

No vehicle over 5 tons is permitted in the cemetery.

** Confirm understanding of scope of work

Washington Cemetery Historic Trust
Monument Repair - Phase 5E
The Monument Company

8-Mar-2000

Page 1 of 1

Lot No.	Name	No.	Size*	Scope*	Scope of Work	Repair	Cleaning	Pin Characteristics		
								Number of Pins	Pin Diameter	Pin Length
C-005	Kumke	1	S	D	Drill, pin, & rejoin on existing base & foundation	80	20	1	0.750	6
C-016	Gaedke	1	M	D	Drill, pin, & rejoin smaller one on existing base & found.; clean bot	40	10	1	0.750	8
C-150	Dickey	2	M	D	Drill, pin, & rejoin on existing bases & foundations	80	20	1	0.750	6
C-150	Wagner	1	M	D	Drill, pin, & rejoin on existing base & foundation (clean 2nd one)	80	40	1	0.750	6
D-114	McMahon	1	M	D	Drill, pin, & rejoin on existing base & foundation	160	20	2	0.563	8
F-079	Pruce	1	M	F	Level on new foundation (was repaired in Phase 2B)	250	25	2	0.750	6
F-079	Pruce	1	C	F	Straighten and clean cradle and coping	250	75	--	--	--
F-082	Praytor/Campbell	1	M	D	Drill, pin, & rejoin on existing base & foundation (add one pin)	120	30	1	0.750	12
F-082	Lewis	1	S	R	Repair two loose chunks, and rejoin	40	15	--	--	--
G-011	Lemkie/Florence	1	M	D	Drill, pin, & rejoin on existing base & foundation	60	25	1	0.750	16
G-012	Heinzelberger	1	L	D	Drill, pin, & rejoin on existing base & foundation (G-11 in photo)	80	30	1	0.750	24
G-018	Vanden	1	S	F D	Raise and set on new foundation; drill and pin	125	15	2	0.500	6 (nylon)
G-018	Hollyway	1	S	F R L	Repair and set into new limestone slab on new found. per THC (like	400	10	--	--	
G-022	Keister	1	M	D	Drill, pin, & rejoin on existing base & foundation	160	15	2	0.750	6
G-022	Pech	2	M	D	Drill, pin, & rejoin on existing bases & foundations; clean cradles	80	80	2	0.750	10
G-038	Belitz	1	M	D	Drill, pin, & rejoin on existing base & foundation	80	20	1	0.750	9
G-077	Davis	1	M	D	Drill, pin, & rejoin on existing base & foundation	80	40	1	0.750	10
G-083	Hayes	1	M	D	Drill, pin, & rejoin on existing base & foundation	80	20	1	0.750	6
G-086	Smith	1	M	D	Drill, pin, & rejoin on existing base & foundation	80	20	1	0.750	9
G-097	Wahlberg/Gustavs	3	M	D	Drill, pin, & rejoin on existing bases & foundations	320	40	4	0.750	6
G-098	Ward	1	S	D	Drill, pin, & rejoin on existing base & foundation	80	25	1	0.750	10
Average cost:										
Total Repairs		25		109	Number to be cleaned: 25	2,725	595			
Total, including cleaning				133			3,320			

*Scope: F - Foundation

D - Drill & pin

S - Shim

R - Repair

*Size: S - Under 2 ft. tall

M - 2-4 ft.

L - 4 -6 ft.

XL - Over 6 ft.

C - cradle

All joints to be secured by pinning and applying adhesive.

No vehicle over 5 tons is permitted in the cemetery.

** Confirm understanding of scope of work

WASHINGTON CEMETERY HISTORIC TRUST

Mailing Address: 4907 Candleleaf Drive, Houston, Texas 77018-1418

Telephone: (281) 531-1956 or (713) 686-3167

8 March 2000

Washington Cemetery
Historic Trust

President
Burt Ballanfant

Secretary
Bernice N. Mistrot

Treasurer
James L. Dally, Jr.

Historian
Gov D. L. Clements

Trustees
Sam Belinoski
Vic Gehring
Julie W. Itz
Herman Lauhoff
Gustave A. Mistrot, III
H. Edgar Moy
A. John Petzold
Carl E. Young
Leona Zaboroski

Mr. John Schlitzberger
The Monument Company

Dear Mr. Schlitzberger,

At a recent trustees meeting, Washington Cemetery Historic Trust voted to award The Monument Company a portion of the work described in your Phase 5 proposal of 29 July 1999. The specific monuments included in this Phase 5E are enumerated on the attached page.

This work is to be completed no later than **30 April 2000**. There are two times during this period during which there shall be no visible work in progress (no monuments lying on the ground, or obvious excavations). Any work started prior to our Spring Open House on Saturday, **25 March**), or Easter weekend (**21-23 April**) must be finished and cleaned up so that the cemetery is neat and tidy on those dates.

Please prepare a contract for this work, to be signed by our President, Mr. Burt Ballanfant, and mail it to him at [REDACTED]

We look forward to continuing to work with you in our ongoing project to restore the many beautiful old monuments in Washington Cemetery. We are currently preparing bid packages for Phase 6.

Very truly yours,

Bernice N. Mistrot
Secretary





















