NOTE 'A'
REMOVE UPPER PART OF BRICK WALL TO LINE WITH BALANCE OF FRONT PARAPET, RESET STONE COPING, FITTING AS REQUIRED, EXTEND FLASHING UP WALL AND UNDER THIS RESET COPING
EXISTING 4" PLBG. VENTS
ROOF AND FLASING ON NEW ADDITION TO REMAIN
NOTE "A"
EXISTING GRAVEL ROOF REMOVED DOWN TO SLAB. EXISTING WALL FLASHING REMOVED. INSTALL NEW 3/4" THICK FIBERGLAS INSULATION OVER FELT MEMBRANE APPLIED TO DECKS, APPLY ONE LAYER OF FELT OVER INSULATION AND FINISH WITH 3 PLY ASBESTOS FELT SMOOTH SURFACE ROOFING. APPLY NEW COMPOSITION FLASHING ON ALL WALLS AT ROOFS AND REPAIR AND REPLACE ALL GALV. IRON COUNTER FLASHING AT PARAPETS, ETC.
EXISTING 20" VENTS
REMOVE THIRD STORY
NOTE. WALLS REMOVED TO BELOW ROOF LEVELS. PROVIDE STEEL ANGLE SUPPORT AND PROVIDE A NEW 16 GA STEEL DECK MEETING EXISTING DECKS, INSTALL EXPANSION JOINT AT CENTER
FLASH AT LARGE ROOF VENTILATORS.
INSTALL NEW 4 lb. LEAD FLASHING AT ALL PLUMBING VENTS THRU ROOFS AS SPECIFIED
D.S.
D.S.
REPEAT
ROOF DRAINS REMOVED TO BELOW ROOF + CAPPED
4"Y 20
REMOVE STAIR RAIL, ETC. AND FILL IN METAL LATH AND PLASTER CLG. AT WELL HOLE
EXIST 4" VENTS
EXISTING FLUES LOWERED AND NEW 6" HIGH CONC. CAP INSTALLED 3'-0" ABOVE PARAPETS
"NOTE 'A'" APPLIES
REPAIR AND REPLACE WHERE REQUIRED ALL ROOF OVERFLOW OUTLETS AND ALL DOWNSPOUTS
NOTE "A"
D.S.
EXISTING OVERFLOW + D.S.
NEW ROOF + INSUL.
INSTALL NEW ROOF
EXP. JNT
OLD SLAB
STL SUPPORTS
EXIST. FL. SLAB
SECTION THRU FILLED IN ROOF
SCALE 1/8"=1'-0
ROOF PLAN - INFIRMARY BLDG.
SCALE 1/8" = 1'-0"
REPAIR
N
COPPER CAP + FLSHG.
1 1/2 x 16 GA STL DECK
VAPOR SEAL
3/4" INSUL.
MEMBRANE
3 PLY SMOOTH SURFACE ROOF
COPPER CVD MEMBRANE + LOOSE INSUL
2X6"S. CONT. BOLT TO L CLIP
6 X 9/16 X 3 1/2" CLIP LS. 2'-0" C.C.
1"
CONT. 2 1/2 X 1/4 X 2 1/2" LS
2 X 1/4 X 2" L UPRIGHTS. 36" C.C.
2 1/2 X 1/4 X 2 1/2" L BRACES 6'-0" C
2 1/2 X 1/4 X 2 1/2" LS AT FLOOR CONT. ANCHOR TO SLAB
EXIST. FL. SLAB
3" SCALE DETAIL. EXP. JNT + SUPPORT