

<u>Project</u>	<u>Days</u>	<u>Hours</u>	<u>Mat'l</u>	<u>Labor</u>
32. Build watchman's room tween deck, install 2 new portholes, wash basin	10	80	\$ 150	\$ 320
33. Build gift shop area tween decks area, install counter	6	48	150	192
34. Chip clean - paint aft peak	8	64	50	256
35. Install privacy divider, center line at crew-head and galley	2	16	15	64
36. Finish clean - chip - paint hold restore ballast	150	1200	600	4,800
37. Build platform in hold under main hatch, install handrail, two ladders to tween deck	30	240	500	960
38. Make and install mast wedges and mast coats, 4 sets	10	80	20	320
39. Install lower top yard crane spurs	10	80		320
40. Rattle down fore-main top gallant rigging, mizzen topmast rigging, fore spreader-lifts	8	64	50	256

